



पत्रांक :- 187 / G-06 / 12

दिनांक 08-2-2024

कोटेशन सूचना

अधोहस्ताक्षरकर्ता द्वारा जनपद महाराजगंज में निर्माणाधीन इगवेयर हाऊस में निम्नलिखित कार्य हेतु मुहर बन्द कोटेशन दिनांक 14.02.2024 को अपराह्न 3.00 बजे तक इस कार्यालय में आमन्त्रित किया जाता है, जो उसी दिन 3.30 बजे उपस्थित कोटेशन दाताओं के समक्ष अधोहस्ताक्षरी अथवा उनके प्रतिनिधि द्वारा खोला जायेगा। कोटेशन खोलने की तिथि में अवकाश हो जाने पर अगले कार्य दिवस में कोटेशन खोला जायेगा।

S. N.	Description of Items	Qty	Time of Completion
1.	Supply and Fixing M.S. Cantiliver Structure: Supply & Fabrication 6.00mtr. Clear span having 1 no. of 6.00mtr long vertical post made of 300.00mm. N.B. pipe as vertical member welded with 10.00mm. thick M.S. plate at bottom & 8.00mm. Plate top for bearing of horizontal span comprising of 40.00 NB. and 25 N.B. pipe bracing as per drawing approved, the work including preparing primer & two coats of synthetic enamel paint fabrication complete in all respect as per direction of E/I.	01 Nos.	07 Days
2.	R.C.C. Foundation:- Construction of one No. RCC Foundation of size 900x900mm. and 1500mm. deep for build up cantiliver structure including earth work excavation, 150mm thick lean concrete in 1:4:8 cement & coarse sand & 20mm, stone grit, concrete in coarse sand and 20mm stone grit in proportion of 1:2:4 grouting of 25mm dia 1000mm long 8 nos. foundation bolt including cost of shuttering and reinforcement as per detailed drawing enclosed.	01 Nos.	
3.	Supply and erection of retro reflective sign board having 4 mm thick aluminium composite panel (ACP) as sign substate face fully covered with 3M Equalent scotchite diamond grade retro reflective prismatic grade sheeting confirm to ASTM D 4956 Type-IV all letters legends and written mater will be computer cut using 3M scotchite Electro cut overlay flim process & with CAS system as per process recommended by original retro reflective sheeting manufacutre etc. complete in all respect. 1. 18.490mtr x 1.22mtr x 1 side = 22.55 sqm. 2. 6.00mtr x 1.83mtr x 2 side = 21.96 sqm. 44.51 sqm.	44.51 Sq. mtr	
4.	Supply erection retro refelective sign board having 4 mm thick aluminium composite panel (ACP) size 1. 18"x8"x22No= 2.01 sqm	2.01 sqm	
5.	Supply Fabrication erection of M.S. Structure frame with M.S. Square pipe (1"x1" sq size) and M.S. Flat 40mm x 5mm and with proper clamping arrangement to be fixed on wall structural steel work in built up tubular section in shoulder mounted including cutting hoisting fixing in position, welded and bolted including fastners etc. Complete finishing with epoxy primer and paint (two or mor coats) complete in all respects.	150 Kg	

नियम व शर्तें:-

- 1- सशर्त कोटेशन मान्य न होंगे।
- 2- दरें समस्त करों सहित होंगी। जी०एस०टी० नियमानुसार देय होगा।

(मनोज कुमार)

अधिशासी अभियन्ता

पत्रांक एवं दिनांक यथोक्त।

प्रतिलिपि:-निम्नलिखित को सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित।

- 1- अधीक्षण अभियन्ता-गोरखपुर 30प्र० आवास एवं विकास परिषद, गोरखपुर।
- 2- इन्चार्ज, कम्प्यूटर सेल, 30प्र० आवास एवं विकास परिषद, मुख्यालय, लखनऊ को परिषद वेबसाइट पर प्रचारित करने हेतु।
- 3- सम्बन्धित सहायक अभियन्ता/अवर अभियन्ता, 30प्र० आवास एवं विकास परिषद, निर्माण खण्ड गोरखपुर-01, गोरखपुर।
- 4- सहायक लेखाधिकारी, 30प्र० आवास एवं विकास परिषद, निर्माण खण्ड गोरखपुर-01, गोरखपुर।
- 5- नोटिस बोर्ड।

अधिशासी अभियन्ता